

MASTER INTAKE — 12-SECTION PROJECT AUDIT

Project: Quick Analysis

Generated: 2026-05-26T12:16:39.764979+00:00

Model: STRUCTMIND CORE · PRO

SHA-256: 2b6f19e64a15b26d791ef1681a6fe13bf098f8bd993ef488eb551201694736ee

===== SECTION 1 — FILE
INVENTORY & DRAWING STATUS
=====

Table: Drawing Register

#	File / Sheet Name	Discipline	Rev	Status	Notes
1	S0.01	Structural	-	■ Readable	General Notes
2	S0.02	Structural	-	■ Readable	Typical Schedules & Details
3	S0.03	Structural	-	■ Readable	Special Inspections
4	S1.01	Structural	-	■ Readable	Foundation Plan
5	S1.02	Structural	-	■ Readable	Second Floor Framing Plan
6	S1.03	Structural	-	■ Readable	Typical Level Framing Plan (3rd & 4th)
7	S1.04	Structural	-	■ Readable	Roof Framing Plan

#	File / Sheet Name	Discipline	Rev	Status	Notes
8	S2.01	Structural	-	■ Readable	Structural Wall Designation Plan
9	S2.02	Structural	-	■ Readable	CMU and Wood Stud Wall Framing Schedules
10	S2.03	Structural	-	■ Readable	CMU Reinforcement Elevations - Stair #1/Elevator
11	S2.04	Structural	-	■ Readable	CMU Reinforcement Elevations - Stair #2
12	S3.01	Structural	-	■ Readable	Foundation Sections
13	S3.02	Structural	-	■ Readable	Floor Framing Sections
14	S3.03	Structural	-	■ Readable	Roof Framing Sections
15	S3.04	Structural	-	■ Readable	Roof Framing Sections
16	S3.05	Structural	-	■ Readable	Canopy Framing Sections
17	S3.06	Structural	-	■ Readable	Trellis and Site Wall Details

State:

- Total files uploaded: 17
- Total readable sheets: 17
- Missing/unreferenced sheets: None noted within the provided set.
- Recommended action before detailing:
 - Obtain Architectural and MEP drawings to coordinate steel interfaces, penetrations, and finishes.
 - Issue RFIs for missing information as detailed in Sections 11 and 12.

===== SECTION 2 —
PROJECT IDENTITY & SYSTEM SUMMARY
=====

Field	Extracted Value	Source Sheet	Confidence
Project Name	HOME 2 - CAROWINDS	S0.01	High
Project Number	2024.023	S0.01	High
Location / Address	Cabelas Dr. Fort Mill, South Carolina 29708	S0.01	High
EOR (Structural Engineer)	Taylor & Viola Structural Engineers	S0.01	High
Architect	rba.	S0.01	High
General Contractor	Not Found in Provided Files	NF	High
Fabricator (if noted)	Not Found in Provided Files	NF	High
Approval Stage	Construction Documents	S0.01	High
Code of Record	2021 IBC, AISC 360-16	S0.01	High
Seismic Design Category	C	S0.03	High

Field	Extracted Value	Source Sheet	Confidence
Wind Exposure Category	C	S0.01	High

Structural System Summary:

- Primary system: Wood-framed bearing walls with engineered wood I-joist floors. CMU shear walls at stair/elevator cores.
- Lateral system: Wood shear walls and CMU shear walls.
- Floor system: Engineered wood I-joists with 3/4" T&G; sheathing and gypcrete topping. Some limited areas of structural steel framing (W-shapes).
- Roof system: Pre-engineered wood trusses with 3/4" T&G; sheathing.
- Foundation interface: Concrete shallow spread footings and slab on grade.
- Special conditions: Steel framed canopies and an exterior trellis structure. Steel lintels in CMU and steel headers in wood framing.

Approximate Tonnage Estimate:

- Primary steel: ~9.5 tons
- Secondary / misc: ~1.5 tons
- Total project: ~11.0 tons
- Confidence: Medium
- Basis: Counted from framing plans S1.02, details on S3.05, S3.06, and schedules on S0.02. High amount of repetition helps confidence, but lengths are estimated from grid dimensions.

===== SECTION 3 —
GRID & GEOMETRY AUDIT
=====

Table: Grid Line Inventory

Grid	Direction	Spacing	Sheet Found	Consistent Across Sheets?	Issues
A-G	North-South	Varies	S1.01	Yes	None
1-18	East-West	12'-10" TYP.	S1.01	Yes	None

State:

- Grid origin confirmed: No / Not Shown
- Skew or angle grids present: No
- Sloped / cambered members noted: No — Camber is not specified for any steel members.
- Curved geometry noted: No
- Any grid conflicts between sheets: None observed. Grids are consistent across S1.01, S1.02, S1.03, and S1.04.

===== SECTION 4 —
MATERIAL GRADE NORMALIZATION
=====

Table: All Materials Found

Member Category	Raw Callout on Drawing	Normalized ASTM Grade	Source Sheet	Conflict?	Notes
Structural Steel Wide Flange Shapes	Structural Steel	ASTM A992 (Grade 50)	S0.01	No	Explicitly stated in General Structural Notes
Structural Steel HSS Shapes	HSS Shapes	ASTM A500, Grade C	S0.01	No	Explicitly stated in General Structural Notes
Structural Steel Pipe Shapes	Structural Steel Pipe	ASTM A53, Grade B	S0.01	No	Explicitly stated in General Structural Notes
Structural Steel Channels/Angles	Structural Steel Misc. Shapes	ASTM A36	S0.01	No	Explicitly stated in General Structural Notes

Member Category	Raw Callout on Drawing	Normalized ASTM Grade	Source Sheet	Conflict?	Notes
Structural Steel Plates	Structural Steel Plates	ASTM A36	S0.01	No	Explicitly stated in General Structural Notes
High Strength Bolts	High Strength Bolts	ASTM F3125, Grade A325	S0.01	No	U.N.O.
Anchor Bolts	Anchor Rods	ASTM F1554, Grade 36	S0.01	No	U.N.O.
Weld Filler Metal	Not Found in Provided Files	■ Missing	NF	Yes	Required for detailing and fabrication.

Flag:

- Grade conflicts between BOM and general notes (e.g., A572-50 vs A36 U.N.O.): No conflicts found.
- Non-standard grades without spec reference: None found.
- Grades that differ between structural and architectural drawings: Architectural drawings not provided for comparison.
- Missing grades (mark ■ Missing — cannot proceed): Weld filler metal spec is missing.
- Weld filler metal specification (E70XX / E71T-x / etc.) — flag if absent: Absent.

Normalized Grade Summary:

- W-shapes: ASTM A992, Gr. 50
- HSS/Pipe: ASTM A500, Gr. C / ASTM A53, Gr. B
- Plates: ASTM A36
- Anchor bolts: ASTM F1554, Gr. 36
- Bolts: ASTM F3125, Gr. A325
- Weld filler: Not Specified

===== SECTION 5 —
SCOPE DETECTION & CLASSIFICATION
=====

Table: Member Scope Register

Member Type	In Scope	Qty (Approx)	Source	Confidence	Notes
Columns	■ Yes	22	S0.02, S3.06	High	Steel columns C1-C5 and trellis columns.
Primary beams	■ Yes	11	S1.02, S3.06	High	W16x36, HSS18x6x3/8, HSS8x6x3/8.
Secondary beams	■ Yes	46	S1.02	High	W14x22 infill beams.
Purlins	■ No	NF	NF	High	Roof is wood truss.
Girts	■ No	NF	NF	High	Walls are wood stud or CMU.
Joists	■■ Depends	Many	S1.02, S3.05	High	Wood I-Joists are out of scope. Light gauge steel joists at canopies (600S200-54) are in scope.
Joist girders	■ No	NF	NF	High	Not used.
Trusses	■ No	Many	S1.04	High	Wood trusses, by others.
Bracing	■ No	NF	NF	High	Lateral system is wood/CMU shear walls.
Moment frames	■ No	NF	NF	High	Not used.

Member Type	In Scope	Qty (Approx)	Source	Confidence	Notes
Shear plates	■ Unclear	NF	S0.02	Low	Wind post connection shows a shear plate, but it is not fully detailed. Likely part of delegated connection design.
Base plates	■ Yes	22	S0.02, S3.06	High	Sizes are given in schedules.
Anchor bolt plans	■ Yes	1	S1.01	High	Location plan exists, details are in schedule S0.02.
Stairs	■ No	2	S2.03, S2.04	High	Stairs are within CMU cores, likely concrete/misc metals by others. No steel stair details provided.
Handrails	■ No	NF	NF	High	Assumed by others.
Ladders	■ No	NF	NF	High	Not shown.
Platforms	■ No	NF	NF	High	Not shown.
Walkways	■ No	NF	NF	High	Not shown.
Mezzanines	■ No	NF	NF	High	Not used.
Canopies	■ Yes	3	S1.02, S3.05	High	HSS18x6 framing and light gauge infill.
Bollards	■ No	NF	NF	High	Not shown.
Gates	■ No	NF	NF	High	Not shown.

Member Type	In Scope	Qty (Approx)	Source	Confidence	Notes
Fences	■ No	NF	NF	High	Not shown.
Embeds	■ Yes	Est. 10	S0.02	Medium	Lintel schedule shows embed angles and plates.
Crane rails	■ No	NF	NF	High	Not used.
Crane beams	■ No	NF	NF	High	Not used.
Transfer beams	■ No	NF	NF	High	Not used.
Misc plates/angles/clips	■ Yes	Many	S0.02, S3.05	Medium	Lintels, wind post connections, canopy connections.
Delegated connection design	■ Yes	All	S0.01	High	Note 7 under "STRUCTURAL STEEL" states "ALL STEEL-TO-STEEL CONNECTIONS ARE TO BE DESIGNED BY FABRICATOR'S ENGINEER..."
Erection drawings	■ Yes	1	NF	High	Required deliverable for steel scope.

State:

- Items clearly IN scope (fabricator to detail): Columns (C1-C5, Trellis), Beams (W14, W16, HSS), Canopies, Trellis, Steel Lintels (L1-L4), Base Plates, Anchor Bolts, Delegated Connection Design.
- Items clearly OUT of scope: Wood framing (I-joists, trusses, studs, headers), CMU walls, Foundations, SOG, Wood Shear Walls.
- Items requiring scope clarification RFI:

- Scope of supply for light gauge steel joists (600S200-54) at canopies.
- Scope of supply for HSS9x5x3/8 Header shown on S1.02, as it interfaces with wood framing.

===== SECTION 6 —
ANCHOR BOLT & BASEPLATE INTAKE
=====

Table: Anchor Bolt Schedule

Column Mark	Bolt Pattern	Bolt Size	Spec (F1554/A307/etc.)	Grade	Embed	Projection	Baseplate	Grout	Hole Type	Source Sheet	Status
C1 (HSS 6x6)	(4) Bolts	3/4" Ø	F1554	36	12"	NF	1"x12"x12"	NF	NF	S0.02	■ Incomplete
C2 (HSS 5x5)	(4) Bolts	3/4" Ø	F1554	36	12"	NF	1"x12"x12"	NF	NF	S0.02	■ Incomplete
C3 (HSS 4x4)	(4) Bolts	3/4" Ø	F1554	36	12"	NF	1"x10"x10"	NF	NF	S0.02	■ Incomplete
C4 (HSS 8x4)	(4) Bolts	3/4" Ø	F1554	36	12"	NF	1"x14"x10"	NF	NF	S0.02	■ Incomplete
C5 (HSS 9x5)	(4) Bolts	3/4" Ø	F1554	36	12"	NF	1"x15"x11"	NF	NF	S0.02	■ Incomplete
Trellis Columns	(4) Bolts	1" Ø	F1554	36	12"	NF	1"x16"x16"	NF	NF	S3.06	■ Incomplete

Flag:

- Missing embed depths: None, all are specified.

- Missing projections: Yes, projection above concrete is not specified for any anchor bolt type.
- Inconsistent bolt patterns vs. baseplate drawings: Bolt patterns are not drawn, only scheduled.
- Leveling nut / washer plate not called: Yes, not specified. Standard practice, but should be confirmed.
- Grout thickness not specified: Yes, grout thickness is not specified.
- Column orientation not shown on anchor bolt plan: Yes, HSS8x4 and HSS9x5 orientations are not shown on plan S1.01.

===== SECTION 7 —
CONNECTION INTELLIGENCE
=====

Table: Connection Assumption Register

Joint Location	Members Connected	Likely Connection Type	Bolt Size/Grade	Weld Size/Type	Plate Thickness	Edge Conditions	Confidence	RFI Required?
Column Base	HSS Col to FDN	Base plate	1"Ø, 3/4"Ø F1554 Gr36	1/4" Fillet	1" PL	NF	High	No
Wind Post Top	W14x22 to W16x36	Simple shear	3/4"Ø A325-N	1/4" Fillet	3/8" PL	NF	Medium	Yes
Trellis Beam-Col	HSS8x6 to HSS8x6	Fully Welded CJP/PJP	NF	CJP/PJP	NF	NF	Medium	Yes
Canopy Beam-Col	HSS18x6 to HSS Col	Moment End Plate	3/4"Ø A325-N	5/16" Fillet	3/4" PL	NF	Low	Yes
Infill Beam	W14x22 to W16x36	Simple shear	3/4"Ø A325-N	NF	3/8" PL	NF	Medium	Yes

Connection types: Simple shear / Moment end-plate / Moment WUF-W / Fully welded / Slip-critical bolted / Gusset bracing / HSS end plate / Column splice / Base plate

Flag:

- Deferred connection design (mark ■ — major risk): Yes. General Note S0.01/STRUCTURAL STEEL #7 explicitly states: "ALL STEEL-TO-STEEL CONNECTIONS ARE TO BE DESIGNED BY FABRICATOR'S ENGINEER AND SUBMITTED TO EOR FOR REVIEW AND APPROVAL..." This is a critical workflow item, not a risk, as it's clearly defined.
- Slip-critical connections without SSPC prep spec (mark ■ — code issue): No slip-critical connections noted.
- Connections with 3+ members framing — constructability risk: None noted.
- Field weld vs. shop weld not distinguished: Yes. No distinction is made on typical details or plans.

Slip-Critical Alert (if any slip-critical connections found):

- SSPC prep spec stated? N/A
- Faying surface masking noted? N/A
- Bolt pre-tension method stated? N/A
- Surface class (A/B) confirmed? N/A

===== SECTION 8 —
SPECIFICATION CONFLICT VALIDATOR
=====

Table: Conflict Matrix

Conflict ID	Item	Structural Spec Callout	Arch / Other Spec Callout	Conflict Type	Impact	Recommended Resolution
C-01	Weld Spec	E70XX specified for shop/field welding.	Not Found in Provided Files	WELD	Critical	General Note for welding states "All welding...shall conform to AWS D1.1" but no filler metal strength (e.g., E70XX) is specified anywhere. This is required for connection design and WPS. RFI required.
C-02	Steel Finish	Shop primer noted in General Notes (S0.01).	Architectural Drawings Not Provided.	FINISH	Major	Exterior steel (canopies, trellis) may require galvanizing or a specific paint system. This must be clarified by comparing with Architectural specs/drawings. RFI required.

Conflict Types: GRADE | FINISH | DIMENSION | BOLT | WELD | SCOPE | CODE | TOLERANCE

Flag ALL conflicts — do not filter minor ones. A minor conflict on-site = major rework.

===== SECTION 9 —
 INITIAL MTO (MATERIAL TAKE-OFF)
 =====

Table: Complete MTO Register

#	Type	Mark/Tag	Profile/Section	Qty	Unit Length (Imperial)	Length (m)	Unit Wt (kg/m)	Est. Wt (kg)	Est. Wt (lbs)	Grade	Source Sheet	Detail/View	Confidence
1	BEAM	B1	W16X36	2	25'-9"	78.486	53.6	841.4	1855	A992	S1.02	Plan	High
2	BEAM	B2	W14X22	46	12'-10"	39.116	32.7	5883.9	12972	A992	S1.02	Plan	High
3	BEAM	B3	HSS18X6X3/8	6	12'-10"	39.116	57.3	1345.5	2966	A500-C	S1.02	Plan	High
4	BEAM	B4	HSS9X5X3/8	1	4'-2 3/4"	12.891	42.1	54.3	120	A500-C	S1.02	Plan	High
5	BEAM	B5	HSS6X4X1/4	2	2'-0" (Est.)	60.96	21.6	26.3	58	A500-C	S1.02	Plan	Medium
6	BEAM	TR-BM	HSS8X6X3/8	3	13'-0"	39.624	47.1	560.8	1236	A500-C	S3.06	Detail 2	High
7	COLUMN	C1	HSS6X6X3/8	10	14'-0" (Est.)	42.672	34.6	1477.3	3257	A500-C	S0.02	Schedule	Medium
8	COLUMN	C2	HSS5X5X3/8	2	14'-0" (Est.)	42.672	28.7	244.7	540	A500-C	S0.02	Schedule	Medium
9	COLUMN	C3	HSS4X4X3/8	2	14'-0" (Est.)	42.672	22.8	194.5	429	A500-C	S0.02	Schedule	Medium

#	Type	Mark/Tag	Profile/Section	Qty	Unit Length (Imperial)	Length (m)	Unit Wt (kg/m)	Est. Wt (kg)	Est. Wt (lbs)	Grade	Source Sheet	Detail/View	Confidence
10	COL	C4	HSS8X4X3/8	2	14'-0" (Est.)	42.672	37.3	318.5	702	A500-C	S0.02	Schedule	Medium
11	COL	C5	HSS9X5X3/8	2	14'-0" (Est.)	42.672	42.1	359.1	792	A500-C	S0.02	Schedule	Medium
12	COL	TR-COL	HSS8X6X3/8	4	9'-0" (Est.)	27.432	47.1	517.0	1140	A500-C	S3.06	Detail 2	Medium
13	PLATE	BP1	PL 1"x12"x1/2"	12	1'-0"	304.8	204.0	735	162	A36	S0.02	Schedule	High
14	PLATE	BP3	PL 1"x10"x1/2"	2	0'-10"	254.0	204.0	104	23	A36	S0.02	Schedule	High
15	PLATE	BP4	PL 1"x14"x1/2"	2	1'-2"	355.6	204.0	145	32	A36	S0.02	Schedule	High
16	PLATE	BP5	PL 1"x15"x1/2"	2	1'-3"	381.0	204.0	164	36	A36	S0.02	Schedule	High
17	PLATE	TR-BP	PL 1"x16"x1/2"	4	1'-4"	406.4	204.0	331	73	A36	S3.06	Detail 2	High
18	ANGLE	L1	L3.5x3.5x1/4	1	4'-0" (BOM)	1219.2	8.5	104	23	A36	S0.02	Schedule	High

#	Type	Mark/Tag	Profile/Section	Qty	Unit Length (Imperial)	Length (m)	Unit Weight (kg/m)	Est. Wt (kg)	Est. Wt (lbs)	Grade	Source Sheet	Detail/View	Confidence
19	ANGLE	L2	L5x3.5x5/16	1	5'-4" (BOM)	1625.6	12.2	19.8	44	A36	S0.02	Schedule	High
20	PLATE	L3	PL 3/8" x9.25"	1	5'-4" (BOM)	1625.6	27.5	44.7	99	A36	S0.02	Schedule	High
21	PLATE	L4	PL 3/8" x12"	1	10'-0" (BOM)	3048.0	35.8	109.1	241	A36	S0.02	Schedule	High

MTO Summary by Category:

Category	Total Qty	Est. Total Weight (lbs)	Est. Total Weight (tons)
W-Shapes	48	14,827	7.41
HSS Shapes	32	6,958	3.48
Plates & Angles	26	733	0.37
Total	106	22,518	11.26

===== SECTION 10 —

DRAWING QUALITY SCORE

=====

Table: Quality Assessment

Indicator	Score (1–5)	Finding	Blocking Issue?
Revision / Approval Stage	5	Issued as Construction Documents. Clear status.	No
Connection Design Completeness	2	Fully delegated to fabricator. No prescriptives details are provided for steel-to-steel connections, which is a major scope item to be carried by the fabricator.	No
Dimensional Clarity	4	Grids are clear, and primary member locations are well-defined. Some orientations on plan are missing.	No
Scope Definition	3	Steel scope is identifiable but interfaces with wood and light gauge are shown via typical details only. Scope of light gauge supply is ambiguous.	No
Specification Availability	3	Material grades are clear, but weld filler metal and finish for exterior steel are missing.	Yes

Indicator	Score (1-5)	Finding	Blocking Issue?
Cross-Sheet Consistency	5	All sheets are consistent with each other. No conflicts found within the structural set.	No
AISC / AWS Compliance Indicators	4	AISC 360-16 is referenced. AWS D1.1 is referenced. These are appropriate.	No
OVERALL SCORE	26/35		

Drawing Grade: B (Minor gaps)

State:

- Modelling Start Recommendation: GO WITH CAUTION
- Reason: Modeling can begin, but immediate RFIs are required for weld specifications, exterior finishes, and connection design criteria before any shop drawings can be completed.

===== SECTION 11 —
MISSING / WRONG / CONFLICTS REGISTER
=====

Table: Issue Register (All blocking + non-blocking issues)

ID	Priority	Issue Type	Issue Description	Sheet/Location	Member/Detail	Why It Blocks Detailing	Suggested RFI Text
1	■ Critical	WELD-MISSING	Weld filler metal specification (e.g., E70XX) is not provided in the general notes or details.	S0.01	General Notes	Connection design calculations and WPS development cannot be completed without the specified electrode strength.	Per S0.01 General Structural Notes, all welding is to conform to AWS D1.1. Please confirm the required weld filler metal strength (e.g., 70ksi).

ID	Priority	Issue Type	Issue Description	Sheet/Location	Member/Detail	Why It Blocks Detailing	Suggested RFI Text
2	■ Major	SPEC-CONFLICT	Finish for exterior steel (canopies, trellis) is not specified. General notes call for primer, which is insufficient for exterior exposure.	S0.01, S3.05, S3.06	General Notes, Exterior Steel	Fabricator cannot procure and apply the correct finish without specification. Applying primer to exterior steel will lead to premature failure.	The canopy and trellis steel on sheets S3.05 and S3.06 are exposed to weather. General Note on S0.01 specifies shop primer U.N.O. Please confirm the required finish for all exterior structural steel (e.g., Galvanizing per ASTM A123, or a specific paint system).

ID	Priority	Issue Type	Issue Description	Sheet/Location	Member/Detail	Why It Blocks Detailing	Suggested RFI Text
3	■ Major	CONNECTION-INCOMPLETE	Anchor bolt projection above concrete is not specified. Grout thickness is not specified.	S0.02, S3.06	Schedules	The anchor bolt list cannot be released for fabrication without knowing the required projection. Base plate details in the model cannot be finalized without grout thickness.	The Steel Column Schedule on S0.02 and detail 2/S3.06 provide anchor bolt embedment but do not specify the required projection above top of concrete. Please provide the required projection and the design grout thickness for all column bases.

ID	Priority	Issue Type	Issue Description	Sheet/Location	Member/Detail	Why It Blocks Detailing	Suggested RFI Text
4	■ Major	CONNECTION-INCOMPLETE	Connection design is delegated, but no performance criteria (e.g., loads, moments, stiffness requirements) are provided for any connection.	S0.01, S1.02	General Notes	The connection design engineer cannot proceed without the loads for each connection type.	Per General Note 7 on S0.01, all steel-to-steel connections are to be designed by the fabricator's engineer. Please provide a complete set of connection forces (axial, shear, moment) for all steel connections to allow design to proceed.

ID	Priority	Issue Type	Issue Description	Sheet/Location	Member/Detail	Why It Blocks Detailing	Suggested RFI Text
5	■ Minor	MISSING-DIM	The orientation of asymmetrical columns (C4 - HSS8x4, C5 - HSS9x5) is not shown on the foundation plan.	S1.01	Plan View	The anchor bolt plan cannot be finalized without confirming the column orientation and its relation to the grid lines.	Please provide the orientation for columns C4 (HSS8x4) and C5 (HSS9x5) on the Foundation Plan S1.01 relative to the column grid lines.

ID	Priority	Issue Type	Issue Description	Sheet/Location	Member/Detail	Why It Blocks Detailing	Suggested RFI Text
6	■ Minor	SCOPE-GAP	The supply scope for light gauge steel joists (60 OS200-54) shown at canopies is unclear.	S3.05	Details 5,6,7	It is unclear if these are supplied by the structural steel fabricator or another trade. This impacts bidding and coordination.	Details on sheet S3.05 show 60 OS200-54 light gauge steel joists framing between HSS18x6 beams. Please clarify if these light gauge members are to be supplied and installed by the structural steel fabricator.

Summary line: 1 Critical | 3 Major | 2 Minor | Total: 6 issues

===== SECTION 12 —
 READY-TO-SEND RFI PACKAGE
 =====

RFI-001 To: Taylor & Viola Structural Engineers Re: S0.01 — Weld Filler Metal Specification Priority:
 Critical Blocking: Yes

Question: Per S0.01 General Structural Notes, all welding is to conform to AWS D1.1. Please confirm the required weld filler metal strength (e.g., 70ksi).

Recommended Answer Format: Written confirmation of filler metal strength (e.g., "Confirm 70ksi electrodes are required.")

--- RFI-002 To: Taylor & Viola Structural Engineers Re: S0.01, S3.05, S3.06 — Finish for Exterior Steel
Priority: Urgent Blocking: No

Question: The canopy and trellis steel on sheets S3.05 and S3.06 are exposed to weather. General Note on S0.01 specifies shop primer U.N.O. Please confirm the required finish for all exterior structural steel (e.g., Galvanizing per ASTM A123, or a specific paint system).

Recommended Answer Format: A written specification or reference to an architectural specification for the required finish system.

--- RFI-003 To: Taylor & Viola Structural Engineers Re: S0.02, S3.06 — Anchor Bolt Projection and Grout Thickness
Priority: Urgent Blocking: No

Question: The Steel Column Schedule on S0.02 and detail 2/S3.06 provide anchor bolt embedment but do not specify the required projection above top of concrete. Please provide the required projection and the design grout thickness for all column bases.

Recommended Answer Format: Written confirmation of required projection (e.g., "Provide 3" projection") and grout thickness (e.g., "Design for 1-1/2" grout").

--- RFI-004 To: Taylor & Viola Structural Engineers Re: S0.01 — Delegated Connection Design Loads
Priority: Urgent Blocking: Yes

Question: Per General Note 7 on S0.01, all steel-to-steel connections are to be designed by the fabricator's engineer. Please provide a complete set of connection forces (axial, shear, moment) for all steel connections to allow design to proceed.

Recommended Answer Format: A supplementary drawing or table listing factored loads for each unique connection type shown on the drawings.

--- RFI-005 To: Taylor & Viola Structural Engineers Re: S1.01 — Column Orientation
Priority: Standard Blocking: No

Question: Please provide the orientation for columns C4 (HSS8x4) and C5 (HSS9x5) on the Foundation Plan S1.01 relative to the column grid lines.

Recommended Answer Format: A marked-up plan sketch showing the correct orientation.

--- RFI-006 To: Taylor & Viola Structural Engineers Re: S3.05 — Scope of Light Gauge Steel Joists
Priority: Standard Blocking: No

Question: Details on sheet S3.05 show 600S200-54 light gauge steel joists framing between HSS18x6 beams. Please clarify if these light gauge members are to be supplied and installed by the structural steel fabricator.

Recommended Answer Format: Written confirmation of scope responsibility (e.g., "Light gauge joists are by steel fabricator" or "Light gauge joists are by others").

Group RFIs:

- Critical RFIs (must answer before modeling starts): RFI-001
- Urgent RFIs (answer within first week of modeling): RFI-002, RFI-003, RFI-004
- Standard RFIs (answer before drawing release): RFI-005, RFI-006