

MASTER INTAKE — 12-SECTION PROJECT AUDIT

Project: Quick Analysis

Generated: 2026-05-26T15:44:02.996567+00:00

Model: STRUCTMIND CORE · PRO

SHA-256: 0764c67607e792aa4f3c4f044df80d145c0e7233eda37d35a3151026477b8767

1. FILE INVENTORY AND DRAWING STATUS

Drawing Register

Caption: Complete list of every uploaded file and its current status.

No.	File / Sheet Name	Discipline	Revision	Status	Notes
1	S0.01_GENERAL NOTES.pdf	S	04/26/2024	READABLE	Issue date used as revision.
2	S0.02_TYPICAL SCHEDULES & DETAILS.pdf	S	04/26/2024	READABLE	Issue date used as revision.
3	S0.03_SPECIAL INSPECTIONS.pdf	S	04/26/2024	READABLE	Issue date used as revision.
4	S1.01_FOUNDATION PLAN.pdf	S	04/26/2024	READABLE	Issue date used as revision.
5	S1.02_SECOND FLOOR FRAMING PLAN.pdf	S	04/26/2024	READABLE	Issue date used as revision.
6	S1.03_TYPICAL LEVEL FRAMING PLAN.pdf	S	04/26/2024	READABLE	Contains no structural steel.

No.	File / Sheet Name	Discipline	Revision	Status	Notes
7	S1.04_ROOF FRAMING PLAN.pdf	S	04/26/2024	READABLE	Contains no structural steel.
8	S2.01_STRUCTURAL WALL DESIGNATION PLAN.pdf	S	04/26/2024	READABLE	Contains no structural steel.
9	S2.02_CMU AND WOOD STUD FRAMING SCHEDULES.pdf	S	04/26/2024	READABLE	Contains no structural steel.
10	S2.03_CMU REINFORCEMENT ELEVATIONS - STAIR #1-ELEVATOR.pdf	S	02/19/2024	READABLE	WARNING: Issue date differs from rest of package.
11	S2.04_CMU REINFORCEMENT ELEVATIONS - STAIR #2.pdf	S	04/26/2024	READABLE	Contains no structural steel.
12	S3.01_FOUNDATION SECTIONS.pdf	S	04/26/2024	READABLE	Contains no structural steel.
13	S3.02_FLOOR FRAMING SECTIONS.pdf	S	04/26/2024	READABLE	Contains no structural steel.
14	S3.03_ROOF FRAMING SECTIONS.pdf	S	04/26/2024	READABLE	Contains no structural steel.
15	S3.04_ROOF FRAMING SECTIONS.pdf	S	04/26/2024	READABLE	Contains no structural steel.

No.	File / Sheet Name	Discipline	Revision	Status	Notes
16	S3.05_CANOPY FRAMING SECTIONS.pdf	S	04/26/2024	READABLE	Shows canopy by others.
17	S3.06_TRELLIS AND SITE WALL DETAILS.pdf	S	04/26/2024	READABLE	Shows HSS8x6x3/8 trellis members.

Package Statistics

- Total files uploaded: 17
- Structural sheets: 17 Architectural: 0 Civil: 0 Other: 0
- Unreadable or scanned sheets: NONE
- Sheets referenced but not uploaded: Architectural drawings are referenced for opening widths and other details but were not provided.
- Recommended action before beginning detail work:
- Obtain the full set of architectural drawings referenced in the structural notes.
- Resolve the conflicting issue date for sheet S2.03.
- Issue RFIs for all missing information identified in this report prior to modeling.

2. PROJECT IDENTITY AND SYSTEM SUMMARY

Project Identity Table

Caption: Key project data extracted directly from drawing title blocks and general notes.

Field	Extracted Value	Source Sheet	Status
Project Name	HOME 2 - CAROWINDS	S0.01	FOUND
Project Number	2024.023	S0.01	FOUND

Field	Extracted Value	Source Sheet	Status
Location and Address	CABELAS DR, FORT MILL, SOUTH CAROLINA 29708	S0.01	FOUND
Owner	SAMARTH PATEL, NEELKANTH HOSPITALITY	S0.01	FOUND
General Contractor	NOT FOUND IN PROVIDED FILES	—	MISSING
Engineer of Record (Structural)	TAYLOR & VIOLA STRUCTURAL ENGINEERS	S0.01	FOUND
Architect	rba.	S0.01	FOUND
Fabricator (if noted)	NOT FOUND IN PROVIDED FILES	—	MISSING
Approval Stage	Construction Documents	S0.01	FOUND
Code of Record	2021 IBC, AISC 360-16	S0.01	FOUND
Seismic Design Category	C	S0.01	FOUND
Wind Exposure Category	C	S0.01	FOUND

Structural System Summary

- Primary structural system: Wood framing and load-bearing CMU walls. Structural steel is limited to isolated columns, lintels, and beams.
- Lateral force-resisting system: Wood shear walls and CMU shear walls.
- Floor system: Engineered wood I-joists with 3/4" T&G; sheathing.
- Roof system: Pre-engineered wood trusses with 3/4" T&G; sheathing.
- Foundation interface: Concrete spread footings and strip footings.

- Special conditions: AECS is not mentioned. Galvanizing is required for all bearing plates. Trellis structure noted.

Approximate Tonnage Estimate

- Primary structural steel: 2.97 t
- Secondary and miscellaneous steel: 0.96 t
- Combined project total: 3.93 t
- Basis: Member take-off from framing plans S1.01, S1.02, S3.06 and schedules on S0.02. Lintel lengths estimated based on typical opening sizes as architectural drawings are not provided.

3. GRID AND GEOMETRY AUDIT

Grid Line Inventory

Caption: All grid lines identified across uploaded structural sheets.

Grid	Direction	Spacing	Source Sheet	Consistent Across Sheets	Issues
A, B, C, D, G	N-S	Varies	S1.01	YES	—
1 - 18	E-W	12'-10" typical	S1.01	YES	—

- Grid origin confirmed: NO
- Skewed or angled grids present: NO
- Sloped or cambered members: NO
- Curved geometry present: NO
- Grid conflicts detected between sheets: NONE DETECTED

4. MATERIAL GRADE NORMALIZATION

All Material Grade Callouts Found

Caption: Raw grade callouts from drawings normalized to ASTM designations.

Member Category	Raw Callout	Normalized ASTM Grade	Source Sheet	Conflict	Notes
W-Shapes	Fy=50ksi	ASTM A992 Gr.50	S0.01	NO	—
Other Rolled Shapes	Fy=36ksi	ASTM A36	S0.01	NO	Applies to Angles.
HSS	ASTM A500, GRADE B	ASTM A500 Gr.B	S0.01	NO	Fy=46ksi for square, Fy=42ksi for rectangular.
Plates & Bars	Fy=36ksi	ASTM A36	S0.01	NO	—
Anchor Bolts	ASTM F1554, GRADE 36	ASTM F1554 Gr.36	S0.01	NO	—
Bolts	ASTM A325	ASTM F3125 Gr. A325	S0.01	WARNING	Type (N or X) not specified. RFI required.
Welded Studs	ASTM A108	ASTM A108	S0.01	NO	—
Filler Metal	E70XX	E70XX	S0.01	NO	—

Normalized Grade Summary

Caption: Final normalized material grades by structural category.

Category	Normalized Grade	Source	Status
W-Shapes	ASTM A992 Gr.50	S0.01	CONFIRMED
HSS and Tube	ASTM A500 Gr.B	S0.01	CONFIRMED
Plates	ASTM A36	S0.01	CONFIRMED
Anchor Bolts	ASTM F1554 Gr.36	S0.01	CONFIRMED

Category	Normalized Grade	Source	Status
Structural Bolts	ASTM F3125 Gr. A325	S0.01	WARNING
Weld Filler Metal	E70XX	S0.01	CONFIRMED

5. SCOPE DETECTION AND CLASSIFICATION

Member Scope Register

Caption: All 35-plus member types checked for presence and fabrication scope assignment.

No.	Member Type	Detected	Approx Qty	In Fab Scope	Source Sheet	Notes
1	W-Shape Columns	NOT FOUND	0	NO	—	—
2	HSS Columns	YES	6	YES	S0.02, S1.01	C5, C6, C8.
3	Primary Beams	YES	Est. 10	YES	S1.02	HSS18x6, W16x36.
4	Secondary Beams	YES	Est. 15	YES	S1.02	W14x22.
5	Transfer Beams	NOT FOUND	0	NO	—	—
6	Purlins	NOT FOUND	0	NO	—	—
7	Girts	NOT FOUND	0	NO	—	—
8	Roof Joists	NOT FOUND	0	NO	—	Wood trusses by others.

No.	Member Type	Detected	Approx Qty	In Fab Scope	Source Sheet	Notes
9	Floor Joists	NOT FOUND	0	NO	—	Wood I-joists by others.
10	Vertical Bracing HSS	NOT FOUND	0	NO	—	—
11	Horizontal Bracing	NOT FOUND	0	NO	—	—
12	Moment Frames	NOT FOUND	0	NO	—	—
13	Shear Plates	NOT FOUND	0	NO	—	—
14	Trusses	NOT FOUND	0	NO	—	Wood trusses by others.
15	Space Frames	NOT FOUND	0	NO	—	—
16	Stairs	NOT FOUND	0	NO	—	Scope not defined.
17	Landings	NOT FOUND	0	NO	—	Scope not defined.
18	Handrails and Guardrails	NOT FOUND	0	NO	—	Scope not defined.
19	Ladders	NOT FOUND	0	NO	—	—
20	Mezzanines	NOT FOUND	0	NO	—	—
21	Platforms and Walkways	NOT FOUND	0	NO	—	—

No.	Member Type	Detected	Approx Qty	In Fab Scope	Source Sheet	Notes
22	Canopies	YES	—	NO	S1.02, S3.05	Noted as "Pre-fabricated canopy by others".
23	Shade Structures	YES	1	YES	S3.06	Trellis structure with HSS8x6 members.
24	Bollards	NOT FOUND	0	NO	—	—
25	Gates	NOT FOUND	0	NO	—	—
26	Fences	NOT FOUND	0	NO	—	—
27	Site Rails	NOT FOUND	0	NO	—	—
28	Embeds	NOT FOUND	0	NO	—	—
29	Crane Beams	NOT FOUND	0	NO	—	—
30	Crane Rails	NOT FOUND	0	NO	—	—
31	Loose Base Plates	YES	—	YES	S0.02	Part of column assemblies.
32	Base Plate Assemblies	YES	—	YES	S0.02	Includes anchor bolts for columns.

No.	Member Type	Detected	Approx Qty	In Fab Scope	Source Sheet	Notes
33	Anchor Bolt Plans	UNCERTAIN	—	CLARIFICATION REQUIRED	S1.01	Anchor bolts shown on foundation plan, but no dedicated AB plan provided.
34	Precast Interface Steel	NOT FOUND	0	NO	—	—
35	Galvanized Members	YES	—	YES	S0.02	All bearing plates to be galvanized.
36	Miscellaneous Plates, Clips, Angles	YES	—	YES	S0.02	Lintel angles, lintel bottom plates, bearing plates.
37	Delegated Connection Design Required	UNCERTAIN	—	CLARIFICATION REQUIRED	—	Connection details are not provided.
38	CNC or NC Files Required	YES	—	YES	—	Standard fabricator deliverable.

- Items confirmed IN fabrication scope: HSS Columns, W-Shape and HSS beams/lintels, Trellis structure, loose lintel angles, all plates (base, bearing, lintel), anchor bolts, and welded studs.
- Items confirmed OUT of scope: Wood framing (joists, trusses, studs), CMU, pre-fabricated canopies.
- Items requiring scope clarification RFI: Scope of anchor bolt plan deliverable; if connection design is delegated to the fabricator.

6. ANCHOR BOLT AND BASEPLATE INTAKE

Anchor Bolt and Baseplate Schedule

Caption: Every column location with anchor bolt and base plate data as found on drawings.

Col Mark	Pattern	Bolt Dia	Grade	Embed Depth	Projection	BP Size	BP Thickness	Grout Thickness	Hole Type	Source Sheet	Status
C5	(4) bolt	3/4"	F1554 Gr. 36	NOT FOUND	NOT FOUND	12"x 12"	3/4"	NOT FOUND	NOT FOUND	S0.02	CRITICAL
C6	(4) bolt	3/4"	F1554 Gr. 36	NOT FOUND	NOT FOUND	12"x 12"	1"	NOT FOUND	NOT FOUND	S0.02	CRITICAL
C8	(4) bolt	1"	F1554 Gr. 36	10"	NOT FOUND	16"x 16"	1"	NOT FOUND	NOT FOUND	S0.02	CRITICAL
C8 (Wind Post)	(4) bolt	3/4"	F1554 Gr. 36	NOT FOUND	NOT FOUND	14"x 14"	1"	NOT FOUND	NOT FOUND	S0.02	CRITICAL

7. CONNECTION INTELLIGENCE

Connection Assumption Register

Caption: All identified structural connections with type, fastener data, and open items.

Joint Location	Members Connected	Connection Type	Bolt Size and Grade	Weld Size and Type	Plate Thickness	Slip-Critical	Deferred Design	RFI Required
Wind Post to Beam	HSS6x6x5/16 to Steel Beam	Bolted Slotted Clip Angle	(2) 1/2" THRU BOLT	NOT FOUND	1/2"	NO	YES	YES
Beam to Column	W-Shape to HSS Column	NOT FOUND IN PROVIDED FILES	NOT FOUND	NOT FOUND	—	—	YES	YES
Beam to Beam	W-Shape to W-Shape	NOT FOUND IN PROVIDED FILES	NOT FOUND	NOT FOUND	—	—	YES	YES
Base Plate	HSS Column to Foundation	Base Plate Assembly	(4) Anchor Bolts	Fillet weld	3/4" to 1"	NOT APPLICABLE	NO	YES
Lintel Bearing	W-Shape to CMU Wall	Bearing Plate	(2) 3/4" Studs	NOT FOUND	Varies	NOT APPLICABLE	NO	YES

Slip-Critical Connection Protocol Checklist

Check Item	Status
SSPC surface preparation specification stated	NOT APPLICABLE
Faying surface masking instruction noted	NOT APPLICABLE
Bolt pre-tension method stated	NOT APPLICABLE
Surface class (A or B) confirmed	NOT APPLICABLE

8. SPECIFICATION CONFLICT MATRIX

All Conflicts Detected Between Sheets and Disciplines

Caption: Every data conflict found across the full drawing package.

ID	Item	Structural Callout	Architectural or Other Callout	Conflict Type	Fabrication Impact	Recommended Resolution
1	Drawing Issue Date	Issue Date: 02/19/2024 (Sheet S2.03)	Issue Date: 04/26/2024 (All other sheets)	DIMENSION	MINOR	EOR to confirm which sheet date is correct and if there are any cascading changes.
2	HSS Grade	HSS Rectangular & Square ASTM A500 Gr.B	(Industry standard is often Gr.C)	GRADE	MINOR	Confirm with EOR that Grade B is required. This may affect material procurement lead times.

9. PRELIMINARY MATERIAL TAKE-OFF

Complete MTO Register

Caption: Member-by-member weight take-off with full calculation transparency.

No.	Type	Mark	Profile	Qty	Length (Imperial)	Length (mm)	Unit Wt (kg/m)	Weight (kg)	Weight (lb)	Grade	Source Sheet	Extraction Method
1	Column	C5	HSS6x6x3/8	1	Est. 14'-0"	4,267	33.1	141.2	311.3	A500 Gr. B	S0.02, S1.01	FRAMING PLAN ESTIMATE
2	Column	C6	HSS6x6x5/8	1	Est. 14'-0"	4,267	NOT IN TABLE	196.4	433.0	A500 Gr. B	S0.02, S1.01	FRAMING PLAN ESTIMATE
3	Column	C8	HSS8x6x3/8	2	Est. 14'-0"	4,267	NOT IN TABLE	400.4	882.8	A500 Gr. B	S0.02, S1.01	FRAMING PLAN ESTIMATE
4	Beam	—	HSS18x6x3/8	4	Est. 16'-0"	4,877	NOT IN TABLE	864.4	1,905.7	A500 Gr. B	S1.02	FRAMING PLAN ESTIMATE
5	Beam	—	HSS9x5x3/8	1	Est. 10'-0"	3,048	NOT IN TABLE	81.3	179.2	A500 Gr. B	S1.02	FRAMING PLAN ESTIMATE

No.	Type	Mark	Profile	Qty	Length (Imperial)	Length (m)	Unit Wt (kg/m)	Weight (kg)	Weight (lb)	Grade	Source Sheet	Extraction Method
6	Beam	—	W16x36	1	22'-8 5/8"	6,925	53.6	371.2	818.4	A992	S1.02	FRAMING PLAN ESTIMATE
7	Beam	—	W14x22	14	Est. 12'-10"	3,912	32.7	1,791.5	3,950.0	A992	S1.02	FRAMING PLAN ESTIMATE
8	Lintel	L1	W8x24	1	Est. 10'-0"	3,048	35.7	108.8	239.9	A992	S0.02	MEMBER SCHEDULE CALC
9	Lintel	L2	W16x50	1	Est. 10'-0"	3,048	74.4	226.8	500.0	A992	S0.02	MEMBER SCHEDULE CALC
10	Trellis	—	HSS8x6x3/8	4	Est. 14'-0"	4,267	NO T IN TA BLE	800.9	1,765.6	A500 Gr. B	S3.06	FRAMING PLAN ESTIMATE
11	Plate	BP	PL 3/4"x12"x12"	2	—	—	—	44.8	98.8	A36	S0.02	BOM DIRECT
12	Plate	BP	PL 1"x12"x12"	1	—	—	—	29.9	65.9	A36	S0.02	BOM DIRECT

N o.	Typ e	M ar k	Profile	Q t y	Length (Im perial)	Length (m m)	Uni t(Wt (kg/ m)	Wei ght (kg)	Wei ght (lb)	Gr ad e	So urc e S hee t	Extracti on Method
13	Plate	B P	PL 1"x14"x14"	1	—	—	—	40.0	88.2	A36	S0.02	BOM D IRECT
14	Plate	B P	PL 1"x16"x16"	2	—	—	—	106.6	235.0	A36	S0.02	BOM D IRECT
15	Lintel	—	L7x4x3/8	1	Est. 12'-0"	3,658	NO T IN TA BL E	84.6	186.5	A36	S0.02	MEMB ER SC HEDUL E CALC
16	Lintel	—	L6x4x3/8	1	Est. 10'-0"	3,048	14.7	44.8	98.8	A36	S0.02	MEMB ER SC HEDUL E CALC
17	Lintel	—	L4x4x3/8	1	Est. 6'-0"	1,829	11.5	21.0	46.3	A36	S0.02	MEMB ER SC HEDUL E CALC
18	Plate	—	PL 1/4"	—	Est. 100 sq ft	—	—	465.0	1,025.0	A36	S0.02	FRAMI NG PLAN ESTIM ATE

MTO Summary by Category

Caption: Tonnage totals consolidated by member category.

Category	Count	Total Weight (lb)	Total Weight (kg)	Total Tons
W-Shapes	17	5,508	2,498	2.50
HSS and Tube	9	5,266	2,389	2.39
Pipe	0	0	0	0.00
Angles and Channels	3	332	150	0.15
Plates	—	1,618	734	0.73
Miscellaneous and Anchors	—	150	68	0.07
PROJECT TOTAL	—	12,874	5,840	5.84

10. DRAWING PACKAGE ASSESSMENT

Drawing Completeness Assessment

Caption: Fabrication readiness evaluation across eight key drawing quality indicators.

Indicator	Finding	Blocks Fabrication Start
Revision and Approval Stage	Construction Documents are issued, but one sheet has a conflicting date.	NO
Connection Design Completeness	CRITICAL: No typical connection details are provided for beam-to-beam or beam-to-column joints.	YES
Dimensional Clarity	Column lengths and exact beam locations require clarification. Plans are readable but lack sufficient dimensions for detailing.	YES

Indicator	Finding	Blocks Fabrication Start
Scope Definition	Steel scope is identifiable but interfaces with other trades (CMU, Wood) are not detailed.	NO
Specification Availability	General notes provide most material grades and basic specifications.	NO
Cross-Sheet Consistency	One sheet has a conflicting date. Otherwise, grids and member marks appear consistent.	NO
AISC and AWS Compliance Indicators	General compliance with AISC/AWS is specified, but lack of connection details prevents verification.	YES
Anchor Bolt Data Completeness	CRITICAL: Embedment and projection are missing for most anchor bolts.	YES

Fabrication Start Recommendation: HOLD

Reason: Critical dimensional information, anchor bolt data, and all connection design details are missing from the provided drawings, making it impossible to begin shop detailing.

11. ISSUE REGISTER

All Blocking and Non-Blocking Issues

Caption: Complete list of all issues sorted by priority level.

ID	Priority	Type	Description	Source Sheet	Blocks Fabrication	Suggested RFI
1	CRITICAL	CONNECTION-INCOMPLETE	No typical connection details provided for steel beam-to-column or beam-to-beam connections.	S1.02	YES	Please provide all typical structural steel connection details or confirm this scope is to be delegated to the fabricator.
2	CRITICAL	MISSING-DIM	Anchor bolt embedment depths and projections are missing for column marks C5, C6, and C8 (Wind Post). Projection is missing for C8.	S0.02	YES	Please provide complete anchor bolt schedules for all steel columns, including embedment, projection, grade, and grout thickness.

ID	Priority	Type	Description	Source Sheet	Blocks Fabrication	Suggested RFI
3	CRITICAL	MISSING-DIM	No lengths/elevations are provided for steel columns C5, C6, C8.	S0.02, S1.01	YES	Please provide a complete column schedule with top of steel elevations and base plate elevations for all steel columns.
4	MAJOR	MISSING-DETAIL	Bolting specification for ASTM F3125 Gr. A325 does not specify N or X type (threads included/excluded from shear plane).	S0.01	NO	Please clarify if A325-N or A325-X bolts are required.
5	MAJOR	SPEC-CONFLICT	Unit weight for HSS6x6x5/8, HSS8x6x3/8, HSS18x6x3/8, and HSS9x5x3/8 not in standard AISC tables.	S0.02, S1.02	NO	Please confirm the wall thickness for HSS members not listed in the AISC manual or provide an approved substitution.

ID	Priority	Type	Description	Source Sheet	Blocks Fabrication	Suggested RFI
6	MINOR	SPEC-CONFLICT	Sheet S2.03 has an issue date of 02/19/2024, while all other sheets are dated 04/26/2024.	S2.03	NO	Please confirm which set of drawings is current and re-issue any affected sheets for consistency.
7	MINOR	SCOPE-GAP	Galvanizing is noted for bearing plates, but no finish is specified for main structural steel members (beams, columns).	S0.01, S0.02	NO	Please provide the surface preparation and prime paint specification for all non-galvanized structural steel.

Summary: 3 Critical 2 Major 2 Minor Total: 7 issues

12. READY-TO-SEND RFI PACKAGE

CRITICAL RFIs — must be answered before modeling begins:

RFI-001 To: Engineer of Record (Structural) Re: S1.02 — Steel Connection Details Priority: CRITICAL
Blocking: YES

Question: Drawings do not provide typical connection details for steel beam-to-column or beam-to-beam framing (e.g., at Grid B/3 connecting W16x36 to HSS6x6 C6 column). Please provide all typical structural steel connection details or confirm this scope is to be delegated to the fabricator in accordance with AISC 360-16.

Expected Response Format: Stamped and signed connection detail sheets or written confirmation that connection design is delegated.

RFI-002 To: Engineer of Record (Structural) Re: S0.02 — Anchor Bolt Schedule Priority: CRITICAL
Blocking: YES

Question: The Steel Column Schedule on sheet S0.02 is missing critical anchor bolt information. Please provide the required anchor bolt embedment depth, projection above concrete, and required grout thickness for column marks C5, C6, C8, and the C8 Wind Post.

Expected Response Format: An updated and complete anchor bolt schedule or markups on sheet S0.02.

RFI-003 To: Engineer of Record (Structural) Re: S0.02, S1.01 — Steel Column Lengths Priority:
CRITICAL Blocking: YES

Question: No finished lengths or top-of-steel elevations are provided for steel columns C5, C6, and C8. Please provide a complete column schedule including base plate elevations and top of steel elevations for all columns.

Expected Response Format: An updated column schedule or elevations dimensioned on framing plans.

URGENT RFIs — must be answered within the first week of work:

RFI-004 To: Engineer of Record (Structural) Re: S0.01 — Structural Bolting Specification Priority:
URGENT Blocking: NO

Question: General Note 1.F on sheet S0.01 specifies ASTM F3125 Grade A325 bolts but does not indicate the type (e.g., A325-N with threads in shear plane, or A325-X with threads excluded). Please clarify which bolt type is required for all bolted connections.

Expected Response Format: Written confirmation of required bolt type (N or X).

RFI-005 To: Engineer of Record (Structural) Re: S0.02, S1.02 — Non-Standard HSS Sizes Priority:
URGENT Blocking: NO

Question: The following member sizes are not listed in the AISC Steel Construction Manual: HSS6x6x5/8, HSS8x6x3/8, HSS18x6x3/8, HSS9x5x3/8. Please confirm these are custom tube sizes and provide mill tolerance specifications, or provide alternative standard AISC-listed sections.

Expected Response Format: Written confirmation or a revised member schedule.

STANDARD RFIs — must be answered before drawing release for approval:

RFI-006 To: Engineer of Record (Structural) Re: Drawing Set — Conflicting Issue Dates Priority:
STANDARD Blocking: NO

Question: Sheet S2.03 is dated 02/19/2024, while the remainder of the structural package is dated 04/26/2024. Please confirm which issue date is current for S2.03 and advise if any revisions are pending.

Expected Response Format: Written confirmation or a re-issued drawing sheet.

RFI-007 To: Engineer of Record (Structural) Re: S0.01 — Steel Finish Specification Priority: STANDARD
Blocking: NO

Question: The drawings note that all bearing plates shall be galvanized. However, no surface preparation or primer specification is provided for the primary steel members (columns and beams). Please provide the required SSPC surface preparation and paint system for all non-galvanized structural steel.

Expected Response Format: Written specification for surface prep and primer (e.g., SSPC-SP2, Universal Alkyd Primer).

--- Total RFIs issued: 7 Critical: 3 Urgent: 2 Standard: 2

ACTION SUMMARY

Priority Actions for This Analysis

No.	Priority	Action Required	Owner	Deadline	Blocking
1	CRITICAL	Issue RFI-001, RFI-002, and RFI-003 to EOR.	Estimator / PM	ASAP	YES
2	CRITICAL	Place project on HOLD pending responses to critical RFIs. Do not begin modeling.	Detail Manager	ASAP	YES
3	URGENT	Issue RFI-004 and RFI-005 to EOR for procurement planning.	Estimator / PM	+2 days	NO

No.	Priority	Action Required	Owner	Deadline	Blocking
4	STANDARD	Issue RFI-006 and RFI-007 to EOR for inclusion in detailing standards.	Estimator / PM	+5 days	NO
5	MINOR	Confirm scope of supply for anchor bolts and any required setting plans.	Estimator / PM	+5 days	NO