

FABRICATION ESTIMATE

Project: AI · 04 Structural_selected_2024-05-02_05-14-08am.pdf · Country: USA · Currency: USD

AI TONNAGE	RATE BAND	FINAL (MID)
18.6 t	\$2,400 → \$3,600 / ton	\$55,800

AI-EXTRACTED QUANTITIES (STRUCTMIND CORE)

Metric	Value
Total fabricated tonnage	18.60 t
Distinct members counted	224
Primary material	Mixed A992 W-shapes and A500 HSS
Drawings analysed	17
Confidence	MEDIUM

AI note: Tonnage primarily from second floor framing plan S1.02. Lintel and wind post quantities are estimated due to missing callouts on plans and incomplete member schedules. Includes 7% allowance for connections and plates.

USER-PROVIDED RATE BAND

Input	Low	High
Per-ton cost (user)	\$2,400	\$3,600

ESTIMATE RANGE (LOW · MID · HIGH)

Line	Low	Mid	High
Subtotal	\$44,640	\$55,800	\$66,960
Tax (0%)	\$0	\$0	\$0
GRAND TOTAL	\$44,640	\$55,800	\$66,960

FINAL FABRICATION RANGE

\$44,640 → \$66,960

Mid-point headline: \$55,800 · AI tonnage × your per-ton band · includes USA tax.